1" = 30' scale 30 0 30 60 feet

GENERAL NOTES

1. AREA DRAIN: AS-BS-CI-SP: IRON FLOOR DRAIN WITH GRATE WITH TYPE E LOCKING DEVICE (2 SCREWS ONLY) BY NEENAH FOUNDRY COMPANY, CATALOG NUMBER R-4937-B-TYPE E. PRODUCTS ARE AVAILABLE FROM: ENSITE, INC., POST OFFICE BOX 151, FT. PAYNE, ALABAMA 35967, (800/235-2440).
2. ALL STORM DRAINAGE PIPING TO BE SLOPED AT 1.00 UNLESS OTHERWISE NOTED.
3. CLEANOUTS SHALL BE J.R. SMITH MODEL NO. 4045-V-FD (SEE DETAIL SHEET C3.02). TRASH RECEPTACLES ARE AVAILABLE FROM: CAMBRIDGE DESIGNS, INC., POST OFFICE BOX 900, GREENVILLE, ALABAMA 36037, (800/477-7320).
4. MANHOLE SHALL BE NEENAH R-1772-A (SEE DETAIL SHEET C3.02). TRASH RECEPTACLES ARE AVAILABLE FROM LITCHFIELD INDUSTRIES, 4 INDUSTRIAL DRIVE, POST OFFICE BOX 317, LITCHFIELD, MICHIGAN 49252, (800/444-8329). IN ACCORDANCE WITH A.H.D. SPECIAL DRAWING NO. HH-621-2.
5. CONTRACTOR SHALL INSTALL SITE UTILITIES TO WITHIN 5 FEET OF CONCESSIONS BUILDING.

SEE SHEET C2.01 FOR CONTINUATION

INSTALL DOUBLE 6' GATE (TYP.) (SEE DETAIL SHEET C3.04)

INSTALL TICKET BOOTH (SEE DETAIL SHEET A6.02)

8' FENCE

12' FENCE

INSTALL PLAYGROUND EDGING (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL GAMETIME MODEL NO. E6623 DURASCAPE PLAY STRUCTURE W/6' MIN. CLEAR TO EDGING & PAVEMENT. INSTALL ACCORDING TO MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS.

INSTALL 6' GATE (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL LITCHFIELD INDUSTRIES MODEL NO. 5100 TRASH RECEPTACLE (PERMANENT MOUNT, FLAT BLACK ENAMEL FINISH) INSTALL ACCORDING TO MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS (TYP.- 32 TOTAL) OR APPROVED EQUAL

INSTALL GAMETIME MODEL NO. E6623 DURASCAPE PLAY STRUCTURE W/6' MIN. CLEAR TO EDGING & PAVEMENT. INSTALL ACCORDING TO MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS. OR APPROVED EQUAL.

SHREDDED HARDWOOD MULCH PLAYGROUND SURFACING (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL SCORE LINE IN CONC. PAVEMENT (TYP.) (PATTERN SHOWN IS TYPICAL FOR ALL RADIAL PARTS OF PAVEMENT)

INSTALL 1/2" EXPANSION JOINT IN CONC. PAVEMENT (TYP.) (PATTERN SHOWN IS TYPICAL FOR ALL RADIAL PARTS OF PAVEMENT)

INSTALL LANDSCAPE FENCE (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL BRICK PAVING (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL 7'X19' CONC. PAD FOR CONDENSING UNITS (SEE DETAIL SHEET M1.02) SURROUND PAD W/ WOOD SCREEN FENCE W/ DOUBLE 4' GATE AS SHOWN (SEE DETAIL SHEET C3.03)

INSTALL CAMBRIDGE DESIGNS MODEL NO. C128 BENCH - 8' LENGTH PERMANENT MOUNT W/ REDWOOD SLATS INSTALL ACCORDING TO MANUFACTURER'S INSTRUCTIONS. 7 BENCHES TOTAL OR APPROVED EQUAL

CUT-OUT FOR TREE GRATE (TYP.) (SEE DETAIL SHEET L2.01)

INSTALL ASPHALT PAVED WALK (TYP.) (SEE DETAILS SHEET C3.02)

BASE LINE

8' FENCE (SEE DETAILS SHEET C3.04 FOR ALL FENCES)

SKINNED INFIELD (TYP.) (SEE DETAIL SHEET C3.03)

INSTALL PICNIC SHELTER (TYP.) (SEE DETAILS SHEET A6.02)

INSTALL GROUND MOUNTED SEATING (TYP.) (SEE DETAIL SHEET C .03)

LIGHT DUTY (TYP.)

6' PC (TYP.)

INSTALL DUGOUT (TYP.) (SEE DETAIL SHEET A6.02)

INSTALL BACKSTOP (TYP.) (SEE DETAILS SHEET C3.04)

INSTALL TICKET BOOTH (SEE DETAIL SHEET A6.02)

CONCESSIONS BUILDING

TYP. DIRECTION OF BRICK RUNNING BOND COURSES

P.O.B. BASE LINE STA. 1+87

R 53.81, E.I. 51.81 (TYP. FOR ALL PAVED FLOOR DRAINS) (SEE DETAIL SHEET C3.03)

CONC. PAVING (TYP.)

INSTALL DOUBLE 5' GATE (TYP.) (SEE DETAIL SHEET C3.04)

12' FENCE (SEE SHEET C3.04 FOR ALL FIELD FENCE DETAILS)

INSTALL 8' GATE (TYP.) (SEE DETAIL SHEET C3.04)

EASY DEVT.

1 2 3 4 5

UTILITY LAYOUT INSET

N.T.S.

RELOCATED FIRE HYDRANT & VALVE IN PLANTING BED

25 L.F. OF NEW 6" WATER LINE

RELOCATE EXISTING FIRE HYDRANT & VALVE

EX. 1" W

EX. 6" W

3 1/2" W

2 1/2" SERVICE

EX. 6" SAN

CONC BLDG.

EX. 1" W

EX. 6" W

Bargle Wagoner Sumner and Cannon

Engineers, Architects, Planners, Landscape Architects and Surveyors

FIELD AREA LAYOUT AND UTILITY PLAN

CULLMAN FAMILY RECREATION COMPLEX

FOR

CULLMAN PARK AND RECREATION FOUNDATION BOARD

CULLMAN, ALABAMA

DR	CHK	DATE	DESCRIPTION
			ORIGINAL ISSUE

C1.02

FILE NO: 17067-01

B.O.